

Notes:

- 1. ALL INTERCONNECTING PIPE AND FITTINGS SHALL BE INSTALLED BY THE CONTRACTOR.
- 2. ALL PIPING SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 99, 2005 EDITION. PIPING LAYOUT IS DIAGRAMMATIC ONLY. FINAL ARRANGEMENT WILL BE SITE SPECIFIC. CONTRACTOR WILL BE RESPONSIBLE FOR FIELD VERIFICATION AND COORDINATING ACTUAL LOCATION WITH ALL OTHER TRADES.
- 3. CONTRACTOR SHALL VERIFY MOTOR VOLTAGE, PHASE AND AMP RATINGS BEFORE STARTING ELECTRICAL INSTALLATION; AND MAKE CERTAIN THE VOLTAGE SUPPLIED BY THE HOSPITAL IS THE SAME.
- 4. THE ROOM REQUIRES DEDICATED MECHANICAL VENTILATION WITH AN ALLOWABLE TEMPERATURE VARIANCE OF 40° TO 105°F. (FOR HIGHER AMBIENTS, CONSULT FACTORY)
- 5. ELECTRICAL POWER SHALL BE SUPPLIED FROM THE EQUIPMENT SYSTEM BRANCH OF THE ESSENTIAL ELECTRICAL SYSTEM (EMERGENCY POWER).
- 6. EQUIPMENT, INSTALLATION, AND TESTING OF THE MEDICAL VACUUM SYSTEM SHALL COMPLY WITH NFPA 99, 2005 EDITION, AND ALL STATE AND LOCAL CODES OR ORDINANCES.
- 7. WIRE LAG & HIGH TEMP. ALARM REMOTE CONTACTS IN THIS CONTROL SYSTEM TO MASTER ALARM SYSTEM AS REQUIRED BY NFPA 99.
- 8. ALL ACCESSORIES, PIPE AND FITTINGS, EXCEPT DISCHARGE SILENCERS, BEYOND INLET AND DISCHARGE PORTS ARE SUPPLIED AND INSTALLED BY OTHERS.
- 9. WHEN DETERMINING THE TOTAL PIPE LENGTH,
  AND ALL THE STRAIGHT LENGTHS OF PIPE TOGETHER
  IN ADDITION TO THE NUMBER OF ELBOWS TIMES THE
  EFFECTIVE PIPE LENGTH FOR THAT PIPE SIZE.
  (SEE EQUIVALENT PIPE LENGTH TABLE & EXAMPLE
  CALCULATION IN THE O&M MANUAL)

EXHAUST PIPE SIZE TABLE					
UNIT SIZE	PIPE LENGTH				
DX 3HP	0-100'	101'-400'	401'-500'		
	1.50" NPT	2.00" NPT	3.00" NPT		
DX 5HP	0-75'	76'-500'			
	2.00" NPT	3.00" NPT			
DX 7.5HP	0-400'	401'-500'			
	3.00" NPT	4.00" NPT			

EFFECTIVE PIPE LENGTH FOR ELBOWS				
PIPE SIZE (IN)	1.50" NPT	2.00" NPT	3.00" NPT	
EFF. PIPE LENGTH (FT)	4	4.9	7.9	





rm F-007 Rev. 01